

# Sullivan Branch Stream Restoration



**STRAUGHAN  
ENVIRONMENTAL**

c r e a t i n g   a   s u s t a i n a b l e   w o r l d

[www.straughanenvironmental.com](http://www.straughanenvironmental.com)

# Urbanization of Chesapeake Bay watershed has resulted in

- Increase in impervious surface
- Excess erosion
- Sediment plumes
- Stream degradation
- Disconnected floodplains





# Increased development changes the hydrology ; natural channels essentially unravel...

## Problems

- Bed erosion
- Bank erosion
- Tree loss
- Channel incision
- Disconnected floodplains
- Water Quality degradation
- Sediment loads
- Undermining of outfall structures



# Low impact development (LID) strategies offer hope for the future


- Stormwater management strategy
  - Includes land planning and engineering design to mimic predevelopment hydrology
- Goal of LID
  - Infiltrate, store, filter and evaporate runoff
  - Manage stormwater at the surface
  - Protect streams and natural resources
- LID strategies
  - Bioswales
  - Bioretention (raingardens)
  - Infiltration facilities
  - Functional landscapes

*Low impact  
design can  
reduce impacts  
of future  
development  
and  
redevelopment*



Prince Frederick County, Maryland

# SULLIVAN BRANCH



A stream suffering from the effects of increased urbanization




**STRAUGHAN  
ENVIRONMENTAL**

**c r e a t i n g   a   s u s t a i n a b l e   w o r l d**

[www.straughanenvironmental.com](http://www.straughanenvironmental.com)

# Sullivan Branch

- Coastal plain
- Restoration at headwaters
- West Chesapeake area sub-basin
- 15 acre drainage area
- 62% imperviousness



c r e a t i n g   a   s u s t a i n a b l e   w o r l d

[www.straughanenvironmental.com](http://www.straughanenvironmental.com)




# Sullivan Branch Problems



- Failing/undersized outfalls
- Bank erosion
- Severe channel incision
- Sediment settling in wetland of Special State Concern
- Falling trees



# Geomorphic Assessment



- Three distinct reaches



creating a sustainable world

[www.straughanenvironmental.com](http://www.straughanenvironmental.com)



# Reach 1

- Laterally and vertically unstable
- Unable to access floodplain
- Steep slope
- Severe erosion
- Intermittent flow



# Reach 2

- Moderately unstable
- Decrease in bank height
- Decrease in slope
- Transitional reach





# Reach 3

- Vertically and laterally stable
- Dimensions consistent with regional curve
- Access to floodplain
- Reference reach



# Design Goals

- Reduce sediment/ bank erosion
- Allow access to floodplain
- Increase channel stability
- Stabilize outfalls
- Reduce tree impacts






# Design Options

1. Grade back existing banks
  - Significant tree impacts
2. Raise channel invert
  - Large amount of fill
  - Sandy soils compromise stability
3. Combine stormwater mgmt. with natural channel design
  - Agency approval



# 3rd Option



# Stormwater Management Practices



- Fill and re-vegetate tributaries
- Pipe upland runoff
- Create forebay to dissipate energy and improve water quality



# Natural Channel Design



- Stream flows from forebay
- Grade back banks
- Create bankfull and 2-year floodplain benches





# Natural Channel Design



- Create meander geometry based on reference reach
- Keeping a majority of the restored channel within the existing channel to decrease tree impacts



# Bio-Engineering

- Re-vegetate with native vegetation (including Bald Cypress)
- Coir fiber rolls along meander bends
- Woven coir mattress
- Live stake installation





# Structures

- Rock cross vanes
- Step pools
- J-hook vanes



# Address localized erosion

- Bank erosion at meander bends downstream of grading
- Rock cross vanes & J-hook vanes installed to convey flow away from eroding banks





# Stabilize Tributary 5

- Receives drainage from SHA parking lot
- Replace failing riprap
- Create plunge pool



# Project Specifics

- December 2005: Initiation of geomorphic assessment
- April 2007: Plans finalized
- January -February 2009: Stream construction
- 2009-2014: Post construction monitoring
- Construction cost: \$200,000



# Lessons Learned

- Agency coordination early on
- Develop design based on unique site conditions
- Integration of several approaches necessary for success
- Minimizing tree impacts important aspect in design





# Questions?



**STRAUGHAN  
ENVIRONMENTAL**

c r e a t i n g   a   s u s t a i n a b l e   w o r l d

[www.straughanenvironmental.com](http://www.straughanenvironmental.com)