A Past River for a Future Arizona Salt River Environmental Restoration Project





Brian M. Murphy, P.E., CDM Janelle Moyer, P.E., HDR Brendan Fox, WGA Brian Kenny, USACE Chris Ewell, City of Phoenix August 1, 2011









Presentation Outline

Janelle Moyer, P.E., HDR

- Overview
- Goals
- Components

Brian M. Murphy, P.E., CDM

- Channel Restoration
- Next Steps




Project Location

 Rio Salado Oeste is an 8-mile reach of the Salt River in Phoenix, Arizona

COCONINO NAVAJO APACHE PINAL COCHISE Legend Rio Salado Oeste Project

Project Team

- Implemented by USACE, Los Angeles District
- Project partner City of Phoenix (COP)
- Habitat design Wass Gerke & Associates Inc.
- Engineering design HDR | CDM Joint Venture
 Team




Project Timeline

- September 2006 Feasibility Study and Environmental Impact Statement (EIS)
 - USACE and COP
- November 2007 Authorization by the Secretary of the Army
 - Water Resources Development Act of 2007
 - (5) Salt River (Rio Salado Oeste), Maricopa County, Arizona.—The project for environmental restoration, Salt River (Rio Salado Oeste), Maricopa County, Arizona: Report of the Chief of Engineers dated December 19, 2006, at a total cost of \$166,650,000 with an estimated Federal cost of \$106,629,000 and an estimated non-Federal cost of \$60,021,000.
- July 2010 Conceptual Design Documentation Report (CDDR)
 - HDR

Currently Underway


- Design Documentation Report (DDR) for Low Flow Channel design for the upstream half (CDM)
- DDR for Pump station and Reservoir supplying water to future habitat (HDR | CDM)

Study Area



Past influences

- Urban development
- Modifications to the river system
- Sand and gravel mining
- Floodplain encroachment







Present condition

- The Salt River is now
 - a "dry river" that flows only ephemerally from storm runoff and effluent discharge
 - a highly disturbed riverbed
 - has minimal vegetation





RSO is the last and most difficult Salt River reach within Phoenix to be restored

Goals

Future project goals...

- Restore natural ecosystem
- Improve recreation opportunities
- Improve water quality
- Enhance property values
- Reuse reclaimed materials
- Reduce flooding damages





Photos from restored upstream reach, Rio Salado





Components

- 1,000+ acres of re-vegetation
- 100+ acres of wetland habitat
- Sand and gravel mining pit restoration
- Management of 120 acres of invasive species
- Water system to deliver 8 MGD of effluent water to habitat
- Recreational facilities and access
- Roadway network
- River channel restoration







Photos from restored upstream reach, Rio Salado



Components



Recommended Plan



Purpose


- Primary: restore a "functioning" river channel
 - designed based on a natural geomorphic state
 - limit "hard" engineering
- Secondary: protection of habitat and infrastructure
 - keep more frequent runoff events confined to certain areas of the river



Design Criteria

- Utilize the existing low flow channel horizontal alignment where possible
- Follow existing longitudinal slope (vertical alignment)
 - ~0.00076 ft/ft
- Convey approximately the 5-year discharge
 - 20,000 cfs
 - occasional "minor" overbank flooding
- No increase in the regulatory (100-year) water surface elevation
 - 166,000 cfs


Historical Thalweg Alignment








Historical Bank Lines




Recent geologic banks 1870 Bank Lines 1937 Bank Lines 1958 Bank Lines 1979 Bank Lines 1999 Bank Lines

Feasibility Design






Feasibility Design




Preliminary Design



Channel Geometry

- Width, depth, and capacity intended to replicate a naturally occurring low-flow channel in this river system
- Typical channel section
 - trapezoidal
 - bottom width varying from 200 to 385 feet wide
 - 3:1 side slopes





Next Steps

- Channel Restoration
 - 60% design in progress
 - Final design early 2012
- Water infrastructure
 - 60% design complete
 - Final design early 2012
- Design of other project elements
- Estimate Construction start
 - February 2013

Thank you!

For more information contact
 Brian Kenny, USACE

Q & A

